



NATIONAL LAW INSTITUTE UNIVERSITY

Kerwa Dam Road, Bhopal-462044

Phone: (0755)- 2696777(O)

Fax: (0755)- 2696965 (O)

E-mail: nliu@nliu.ac.in

Website: www.nliu.ac.in

Ref. No. 1268 / NLIUB

Date: 12.06.2025

Notice Inviting Quotations

Sealed quotations are invited by Registrar on Behalf of University from reputed Licensed Firms and Contractors registered in CPWD/MPPWD/Other state government PWDs experienced in similar nature of work of Miscellaneous Civil Works. The agency has to strictly visit the site and their rates should be inclusive of material, and labour complete in all respect. **The Agency has to enclose its self-attested copies of PAN Card, GST Number and similar work order experience along with the sealed envelope, if applicable.** The quotations with specific rates for the under mentioned item will be received up to 12.00 pm on 19.06.2025 and will be opened on the same day at 3.30 PM. The taxes, if any are to be clearly mentioned in the sealed quotation. The agency shall download the prescribed format our website: www.nliu.ac.in/tender

The quotation should be addressed to the REGISTRAR, NATIONAL LAW INSTITUTE UNIVERSITY, NEAR KERWA DAM ROAD, BHOPAL-462044, superscribing the envelope with "Miscellaneous Civil Works in the university Boys mess at NLIU, Bhopal".

Terms and Conditions:

1. The work should be completed within 15 (Fifteen) days from the date of work order.
2. Agency must visit the campus after that they quote their rates which should be inclusive of material and labour complete in all respect.
3. The payment will be made based on the actual measurement after satisfactory completion of the work and taxes will be deducted as per Govt rules.
4. All damages done during execution of the work is to be made good by the contractor and nothing extra will be paid separately for the same.
5. It will be the responsibility of the vendor for the safety towards work and the cost towards transportation, packing, loading, unloading etc. will also be borne by the vendor himself.
6. The University reserves the right to accept/reject any or all quotations without assigning any reason.



7. Quotation should reach the Registrar office as mentioned. University is not responsible for any kind of postal delay.
8. The work will be carried out as per relevant Specifications, BOQ and areas/locations as directed complete.
9. If any accident or mishappening occurs due to poor workmanship, the bidder will be wholly responsible for the same.
10. Contractor must visit site before quoting and fully satisfy himself of the site conditions. No Compensation on account of any site difficulties will be entertained, at a later date, after award of the work.
11. No T&P shall be issued to the Contractor. The contractor shall be provided with electricity and water at one point, he shall make his own arrangements for further distribution of electricity, water supply and all other labor, tools, plant and equipment etc. as required for the works complete.
12. In case, the date of submission/opening of tenders happens to be holiday, the tenders shall be received / opened on the next working day.
13. Quotation should reach the Registrar office as mentioned. University is not responsible for any kind of postal delay.
14. Contractor shall abide by labor rules and regulations.
15. All the applicable taxes shall be deducted from bill.
16. Compensation of delay of work will @ 1% per week on account of non-completion of work within stipulated period to a maximum of 10% the value of the work.
17. All material to be used on the work will have to be got approved from the Engineer-in-charge
18. Payment shall be made as per actual quantities of executed works.
19. The University may increase or decrease the scope of work up to 10% of the work order.
20. During execution of work, Engineer may make minor changes in the scope of work as per site conditions or other reasons. Contractor will have no extra claim in his rates for the same.
- 21. GSTIN of NLIU, Bhopal- 23AAAJN0534C1ZV.**
- 22. Electricity and Water Charges @ 1% will be deducted from the bill.**
- 23. Defect liability period: 12 months**



✓
12/06/2015
Registrar

FINANCIAL BIDS

SCHEDULE OF QUANTITY

Ref. No. 1268 / NLIUB

Date: 12.06.2025

Name of the Work: Miscellaneous Civil Works in the University Boys Mess at NLIU, Bhopal.

Name of the Firm/Agency:

Sr. No	Description	Qty	Unit Rate Quoted by the contractor (In Rupees)	Total Amount quoted by Contractor without GST. (In Rupees)
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means over areas (exceeding 30cm in depth. 1.5m in width as well as 10 sqm on plan) including dressing of sides and ramming of bottom disposal of excavated earth, lead up to 50m and lift up to 1.5m, disposed earth to be levelled and neatly dressed. (No extra lift is payable if work is done by mechanical means) All kinds of soil	5 Cum		
2.	Providing and laying in position specified grade of reinforced cement concrete (nominal / design mix with 20mm nominal size graded stone aggregate) excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level : M15 grade concrete	2 Cum		
3.	Structural steel work in single section fixed with or without connecting plate including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	800 KG		
4.	Kota stone slab flooring over 20 mm (average) thick base laid over and jointed with grey cement slurry mixed with pigment to match the shade of the slab including rubbing and mirror polishing complete with base of cement mortar 1 : 4 (1 cement : 4 sand) having thickness of slab 25 mm (Area of slab to be over 0.25 sqm) Note: - Deduction shall be made for not mirror polishing according to item no 11.43	10 Sqm		
5.	Providing and fixing Precoated galvanised iron profile sheets (size, shape and pitch of corrugation as approved by Engineer-in-Charge) 0.50 mm + 0.05 %, total coated thickness with zinc coating 120 gsm as per IS: 277 in 240 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns. Sheet should have protective guard film of 25 microns minimum to avoid scratches while transportation and should be supplied in single length upto 12 metre or as desired by Engineer-in- charge. The sheet shall be fixed using self-drilling /self-tapping screws of size (5.5x 55mm) with EPDM seal, complete upto any pitch in horizontal/ vertical or curved surfaces excluding the	150 Sqm		



	cost of purlins, rafters and trusses and including cutting to size and shape wherever required.			
	Providing and fixing glazing in aluminium door, window, ventilator shutters and partitions etc. with EPDM rubber/ neoprene gasket etc. complete as per the architectural drawings and the directions of engineer-in-charge. With float/frosted/plain glass panes of 4.0 mm thickness (weight not less than 10 kg/sqm) as per site requirement	6 Sqm		
	Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two or more coat applied @0.90 ltr/10 sqm over an under coat of primer applied @ 0.80 ltr/ 10 sqm of approved brand or manufacture.	10 Sqm		
	Providing and laying Ceramic glazed floor tiles 300x300 mm or more (having thickness 6 to 7mm) of 1st quality conforming to IS : 15622 of approved make in any colours and shade laid on 20 mm thick Cement Mortar 1:4 (1 Cement : 4 sand) including pointing the joints with white cement and matching pigment etc., complete. Also include dismantling work if required and necessary disposal outside the university	10 sqm		
	Providing and fixing Ceramic glazed wall tiles 300x450 mm or more (having thickness 6 to 7 mm) of 1st quality conforming to IS: 15622 of approved make in all Colours& shades, except burgundy, bottle green, black laid on 12mm thick bed of Cement Mortar 1:3 (1 Cement: 3 sand)prepad same day when mortar is still green jointed with grey cement slurry @3.3 kg per sqm including pointing the joints with white cement and matching pigments etc., complete. Also include dismantling work if required and necessary disposal outside the university.	10 sqm		
	Filling the gap between tiles and walls with white cement based putty to prevent the entry of termites/cockroach etc. and pointing tiles with required pigment based putty/cement.	50 Rmtr		
	Total Amount without GST			
	GST @18%			
	Total Amount with GST @18%			

Note: 1. All Statutory deduction will be made as per prevailing rates.

Date:
Place:



Signature:
Name:
Designation:
Firm seal: